



NOTES

1. Sediment basins shall be constructed and operational before upslopedland disturbance begins.
2. RISER PIPE BASE:
The riser pipe shall be set at a minimum of 6" in the concrete base.
3. TRASH RACKS:
The top of the riser shall be fitted with trash racks firmly fastened to the riser pipe.
4. SEDIMENT CLEANOUT:
Sediment shall be removed and the sediment basin restored to its original dimensions when the sediment has filled to one-half the height of the riser. Sediment removed from the basin shall be placed so that it will not erode and stabilized similar to other fill material placed on the site.
5. FINAL REMOVAL:
The sediment control structure shall be removed only after the upstream drainage area is stabilized. Dewatering and removal shall not cause sediment to be discharged.

Temporary Sediment Basin Schedule											
Basin No.	Location	Tributary Acreage	Required Basin Volume (67 CY/Ac)	Provided Basin Volume	Control Structure						
					Riser- (A)	Height- (B)	Barrel- (C)	Outlet- (D)	Inlet Elev.- (E)	Trash Rack- (F)	Rack Height- (G)
X	XXXX	X AC.	X C.Y.	X C.Y.	X"	X'	X"	X' @ X%	XXX	X"	X"

	<p>TEMPORARY RISER PIPE</p>	<p>CITY OF GROVE CITY, OHIO</p>		
		<p>STANDARD CONSTRUCTION DRAWING</p>		
		<p>Effective Date 5-12-05</p>	<p>Revision Date 11-15-05</p>	<p>Dwg. No. C-GC-76A</p>