CRITICAL STORM CALCULATIONS

PROJECT NUMBER: CW-16008 DATE: 04/29/2016

CALCULATED BY: RAB

PEAK VOLUME - UNDEVELOPED 1 YEAR STORM HydroCAD 10.00 Results:

Volume = 0.17 Acre-Ft. Flowrate = 0.68 cfs.

PEAK VOLUME - DEVELOPED 1 YEAR STORM HydroCAD 10.00 Results:

Volume = 0.48 Acre-Ft. Flowrate = 3.06 cfs.

PERCENT CHANGE IN VOLUME

0.48 - 0.17 = 0.31 0.31 = 1.824 = **182.4%**

THEREFORE, BASED ON INFORMATION FOUND IN THE MORPC STORMWATER MANUAL, THE CRITICAL STORM IS A 25 YEAR STORM

PERCENT INCREASE		CRITICAL STORM FOR
IS EQUAL TO OR	AND LESS	RUNOFF LIMITATION
GREATER THAN:	THAN:	WILL BE: (YEARS)
0%	10%	1
10%	20%	2
20%	50%	5
50%	100%	10
100%	250%	25
250%	500%	50
500%	-	100

Project: American Self Storage Location: Southwest Blvd.

IMPERVIOUS AREA CALCULATOR

PROJECT NUMBER: CW-16008 DATE: 05/02/2016

CALCULATED BY: RAB

Tabulation of Impervious Areas

All square footages are based on actual identification of entities within the plan, digitally provided from Autodesk - AutoCAD Civil 3D (Version 2010)

Item	Area (sq-ft)	Area (Ac.)
Prop. Building	63750.00	1.463
Parking/Sidewalk/Driveway	70436.52	1.617
	134186.52	
	134100.32	3.080 Acres

Project: American Self Storage Location: Southwest Blvd. Grove City, Ohio

STORM DRAINAGE REQUIRED STORAGE VOLUME

PROJECT NUMBER: CW-16008 DATE: 05/02/2016

CALCULATED BY: RAB

Difference in Increased Runoff Volume

			D	.0.00000		· oranio					
(Based on HydroC	CAD 10.00 Report)			Outlet		100 VEAD		EVEAD			
			_	Outlet		100 YEAR (AF)	(CU-FT)	- 5 YEAR (AF)	(CU-FT)	=	_
				Pond		1.700	74052.00	0.840	36590.40		
Proposed Ref	tention Basin										
Elev.	S.F.	Volume / Ft	t.								STORAGE
800.00	3224	0	(Normal Pool Elevation)		=	0.00					VOLUME
801.00	4036	3622			=	3622.00					
802.00	4919	4470			=	4470.00	S	TORAGE VOLUME	REQUIRED	=	37461.60
803.00	5858	5381			=	5381.00					
804.00	6855	6349			=	6349.00					
805.00	7907	7374			=	7374.00					
806.00	9016	8455			=	8455.00					
806.50	9592	4651			=	4651.00	TOTAL S	TORAGE VOLUME	REQUIRED	=	37461.60 CU. FT.
				Total	=	40302.00				=	37461.60 CU. FT.
							TOTAL S	TORAGE VOLUME	AVAILABLE	=	40302.00 CU. FT.

Pond Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2010 by Autodesk, Inc. v9.25

Monday, May 2, 2016

Pond No. 1 - Storage Volume

Pond Data

Contours -User-defined contour areas. Conic method used for volume calculation. Begining Elevation = 800.00 ft

Stage / Storage Table

Stage (ft) Elevation (ft)		Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)	
0.00	800.00	3,224	0	0	
1.00	801.00	4,036	3,622	3,622	
2.00	802.00	4,919	4,470	8,091	
3.00	803.00	5,858	5,381	13,473	
4.00	804.00	6,855	6,349	19,822	
5.00	805.00	7,907	7,374	27,196	
6.00	806.00	9,016	8,455	35,651	
6.50	806.50	9,592	4,651	40,302	

Culvert / Orifice Structures Weir Structures [A] [B] [C] [PrfRsr] [A] [B] [C] [D] = 0.000.00 0.00 0.00 Rise (in) 0.00 0.00 Crest Len (ft) = 0.000.00 Crest El. (ft) Span (in) = 0.000.00 0.00 0.00 = 0.000.00 0.00 0.00 No. Barrels = 0 0 Weir Coeff. = 0 0.00 0.00 0.00 Invert El. (ft) = 0.000.00 0.00 0.00 Weir Type = ---Length (ft) = 0.000.00 0.00 0.00 Multi-Stage = No No No No Slope (%) = 0.000.00 0.00 n/a N-Value = .000 .000 .000 n/a 0.00 0.00 0.00 = 0 (by Contour) Orifice Coeff. = 0.00Exfil.(in/hr) Multi-Stage = n/aNo TW Elev. (ft) = 0.00

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).

Stage / Storage / Discharge Table

Stage ft	Storage cuft	Elevation ft	Clv A cfs	CIv B cfs	CIv C cfs	PrfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	User cfs	Total cfs
0.00	0	800.00											0.000
1.00	3,622	801.00											0.000
2.00	8,091	802.00											0.000
3.00	13,473	803.00											0.000
4.00	19,822	804.00											0.000
5.00	27,196	805.00											0.000
6.00	35,651	806.00											0.000
6.50	40,302	806.50											0.000

Pond Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2010 by Autodesk, Inc. v9.25

Monday, May 2, 2016

Pond No. 2 - Normal Pool Volume

Pond Data

Contours -User-defined contour areas. Conic method used for volume calculation. Begining Elevation = 795.00 ft

Stage / Storage Table

Stage (ft) Elevation (ft)		Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)		
0.00	795.00	429	0	0		
1.00	796.00	820	614	614		
2.00	797.00	1,294	1,048	1,662		
3.00	798.00	1,853	1,565	3,227		
4.00	799.00	2,496	2,166	5,393		
5.00	800.00	3,223	2,851	8,245		

Culvert / Orifice Structures Weir Structures [A] [B] [C] [PrfRsr] [A] [B] [C] [D] = 0.00 0.00 Rise (in) 0.00 0.00 Crest Len (ft) = 0.000.00 0.00 0.00 Span (in) = 0.000.00 0.00 0.00 Crest El. (ft) = 0.000.00 0.00 0.00 No. Barrels = 00 0 0 Weir Coeff. = 00.00 0.00 0.00 Invert El. (ft) = 0.000.00 0.00 0.00 Weir Type = ---No Length (ft) = 0.000.00 0.00 0.00 Multi-Stage No No = No Slope (%) = 0.000.00 0.00 n/a N-Value = .000.000 .000 n/a = 0.000.00 0.00 0.00 Exfil.(in/hr) = 0 (by Wet area) Orifice Coeff. Multi-Stage = n/aNo No No TW Elev. (ft) = 0.00

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).

Stage / Storage / Discharge Table

Stage ft	Storage cuft	Elevation ft	Clv A cfs	CIv B cfs	CIv C cfs	PrfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	User cfs	Total cfs
0.00	0	795.00											0.000
1.00	614	796.00											0.000
2.00	1,662	797.00											0.000
3.00	3,227	798.00											0.000
4.00	5,393	799.00											0.000
5.00	8,245	800.00											0.000

Calculate Skimmer Size			
Basin Volume in Cubic Feet	40,302 Cu.Ft	Skimmer Size	5.0 Inch
Days to Drain*	2 Days	Orifice Radius	2.0 Inch[es]
	•	Orifice Diameter	4.0 Inch[es]
*In NC assume 3 days to drain			

Estimate Volume of Basin	Length	Width			
Top of water surface in feet			Feet	VOLUME	0 Cu. Ft.
Bottom dimensions in feet			Feet		
Depth in feet			Feet		